

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20,784-00-00

LEASE NAME Achilles

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #15-34

⁷²⁰
~~680~~ Ft. from S Section Line

1980 Ft. from E Section Line

LEASE OPERATOR Pioneer Oil and Gas

SEC. 15 TWP. 4 S RGE. 31 ~~(E) (W)~~

ADDRESS 6925 Union Park Center, Suite 145, Midvale, UT 84047 COUNTY Rawlins

PHONE# (801) 566-3000 OPERATORS LICENSE NO. 30676

Date Well Completed 11/22/91

Character of Well D&A

Plugging Commenced 11/22/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/23/91

The plugging proposal was approved on 11/21/91 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation N/A Depth to Top N/A Bottom T.D. 4550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

12-2-91
RECEIVED

Formation	Content	From	To	Size	Put in	Pulled out
Cedar Hills	water	Surf	254	8 5/8"		none

DEC 02 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Hole filled with 9.6 lb/gal. mud between plugs. Plugs set by displacement method through drill pipe. Plug #1: 25 sacks at 2680', Plug #2: 100 sacks at 1920', Plug #3: 40 sacks at 310', Plug #4: 10 sack surface plug. 15 sack plug in rathole. Total cement used- 190 sacks 60-40 PozMix, 6% Gel, 2 sx floseal.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. N/A

Address P.O. Box 31, Russell, KS 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Anderson

STATE OF Utah COUNTY OF Salt Lake, ss.

Jason G. Blake (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jason G. Blake

(Address) Midvale, Utah (as above)



Subscribed and sworn to before me this 27th day of November, 19 91

John O. Anderson
Notary Public

Commission Expires: