

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-20268-00-00

LEASE NAME PETRASEK "B"

WELL NUMBER #1

2310 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 26 TWP. 4S RGE. 27 ~~EXXK~~(W)

COUNTY Decatur

Date Well Completed 7-16-73

Plugging Commenced 10-29-87

Plugging Completed 10-29-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Edmiston Oil Co., Inc.

ADDRESS 1260 KSB Bldg. Wichita, KS 67202

PHONE#(316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil) Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the (KCC) KDHE Joint District Office prior to plugging this well? yes

Which (KCC) KDHE Joint Office did you notify? Dist. #4 Hays, KS (Carl Goodrow)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing Depth to Top 3412 Bottom 3602 T.D. 3607

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		Surface	279'	8 5/8	279'	None
Lansing		0'	3607	4 1/2	3607	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perfed 2 shots in Anhydrite @ 2010' and shot 2 in the Dakota @ 1410'. Pumped 150 sx of thrifty mix and 4 sx of hulls at 1300#. Shut in at 800# pressure. Pumped 100 sx of thrifty mix and 1 sx of hulls down the backside. Shut in @ 300# pressure.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan License No. _____

Address Box 27 Oakley, KS 67748

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jon M. Callen (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
11-20-87
NOV 20 1987

(Signature) Jon M. Callen

(Address) 1260 KSB Bldg, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 19th day of November, 19 87
Wichita, Kansas

Marilyn E. Gop
Notary Public

My Commission Expires: November 14, 1989



15-039-20268-00-00

DRILLER'S LOG

COMPANY: Edmiston Oil Company
801 First National Bank Bldg.
Wichita, Kansas 67202

ROTARY DRILLING COMMENCED: June 14, 1973

ROTARY DRILLING COMPLETED: June 27, 1973

WELL NAME: PETRASEK "B" #1

LOCATION: NW NE SE Sec. 26-4S-27W
Decatur County, Kansas

CONTRACTOR: E. K. Edmiston Drilling Co., Inc.
801 First National Bank Bldg.
Wichita, Kansas 67202

CASING RECORD: Set 279' of 8-5/8" surface pipe with
235 sx. cement;
Ran 4 1/2" @ 3607' w/225 sx. cement

L O G

Measurements from top of Kelly Bushing (Elevation 2508 K.B.)

Sand	0 - 100
Sand and Shale	1950
Shale	2010
Anhydrite	2040
Shale	2605
Shale and Lime	3010
Lime	3165
Lime and Shale	3450
Lime	3607 RTD

The undersigned, E. K. Edmiston, President of E. K. Edmiston Drlg. Co., Inc., hereby certifies on behalf of said company, that the above log is a true and correct log of the formations encountered in drilling the above well, as reflected by the daily drilling reports.

E. K. Edmiston

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

BE IT REMEMBERED that on this 2nd day of July, 1973, before me, the undersigned, a Notary Public within and for the County and State aforesaid, came E. K. Edmiston, known to me to be the same person who executed the foregoing instrument on behalf of E. K. Edmiston Drilling Company, Inc., and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My Commission Expires:
November 9, 1973



Marilyn E. Fox, Notary Public

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1973

CONSERVATION DIVISION
Wichita, Kansas

BJ-TITAN SERVICES COMPANY

Jon Copy

ORIGINAL

INVOICE DATE
10/29/87

DIRECT BILLING INQUIRIES TO: 713-895-5821	TERMS NET AMOUNT DUE 30 DAYS FROM DATE OF INVOICE	REMIT TO: BJ-TITAN SERVICES P.O. BOX 200416 HOUSTON, TX 77216
----------------------------------------------	------------------------------------------------------------	------------------------------------------------------------------------

PAGE 1	INVOICE NO. YI148
-----------	----------------------

AUTHORIZED BY
281849

PURCH. ORDER REF. NO.

EDMISTON OIL CO., INC.
1260 KSB BLDG
WICHITA

15 039-20268-00-00

KS 67202

NOV 13 1987

WELL NUMBER : B-1

CUSTOMER NUMBER : 03311004

LEASE NAME AND NUMBER <i>PETRUSK B#1</i> <i>PETRASEK</i>	STATE 15	COUNTY/PARISH	CITY	DISTRICT NAME OAKLEY	DISTR. NO 3320
JOB LOCATION/FIELD	MTA DISTRICT	DATE OF JOB 10/29/87	TYPE OF SERVICE LAND-PLUG AND ABANDON		

PRODUCT NUMBER	QUANTITY	DESCRIPTION	UNIT PRICE	U/M	EXTENDED PRICE
10109820	1.00	PUMPING CHARGE	350.00		350.00
10109005	50.00	MILEAGE CHR, FROM NEAREST BASE OF	1.10		55.00
10410504	163.00	CLASS "A" CEMENT	6.00	CF	978.00
10415018	87.00	DIAMIX F	3.62	CF	314.94
10420145	22.00	BJ-TITAN GEL, BENTONITE, BULK SALES	6.75	CM	148.50
10421005	440.00	A-2	1.00	LS	440.00
10422005	63.00	CELLO FLAKE,	1.27	GL	80.01
10424525	5.00	COTTON SEED HULLS PER CWT	14.00	SK	70.00
10940101	315.00	DRAYAGE, PER TON MILE	0.70		220.50
10880085	250.00	MIXING CUSTOMERS MATERIALS, PER CUB	0.95		237.50
SUBTOTAL					2,394.45
DISCOUNT					573.39

02-5020-536-00-6734-01

CEMENT TO PLUG
ACCOUNT

4.00000% STATE TAX
1.00000% COUNTY TAX

2315.56
2315.56
RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1987

CONSERVATION DIVISION
Wichita, Kansas

AX EXEMPTION STATUS

PAY THIS AMOUNT

2,431.34