

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-039-20247 - 00-00

LEASE NAME Petracek A

WELL NUMBER 1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 26 TWP. 4 RGE. 27 (E) or (W)

COUNTY Decatur

Date Well Completed 10/21/72

Plugging Commenced 10/9/02

Plugging Completed 10/9/02

RECEIVED
OCT 15 2002
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Edmiston Oil Company, Inc.

ADDRESS 125 N. Market, Suite 1130 Wichita, KS 67202

PHONE# (316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Richard Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation Lansing-KC Depth to Top 3398 Bottom 3592 T.D. 3595

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
TARKIO	OIL	3071		8-5/8	285	NONE
LANSING	OIL	3398		4-1/2	3594	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set Perforated @ 2025 and 1350. Pumped 50 sx 2/100 lbs of hulls down surface casing annulus, shut in w/100#. Ran tubing to 2000', pumped 110 sx w/300 lbs hulls, circulate cement. Pulled tubing, pumped 65 sx cement in casing, maximum pressure 700 #. Shut in @ 400 #.

Name of Plugging Contractor Poe Well Service License No. 3152

Address PO Box 115, Oberlin, KS 67749-0115

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Edmiston Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jon M. Callen (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Jon M. Callen

(Address) as above

SUBSCRIBED AND SWORN TO before me this 14th day of October, 2002

Trudy Boyer
Notary Public

My Commission Expires: 2/15/05

TRUDY BOYER
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 2/15/05

OR