

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

	X		

Locate well correctly on above
Section Plat

Rawlins County, Sec. 13 Twp. 4S Rge. (E) 33 (W)
Location as "NE/CNW%SW%" or footage from lines C SE-SW
Lease Owner Target Drilling Corporation
Lease Name Spence Well No. 1
Office Address 910 Enterprise Building, Tulsa 3, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-27-61 19 61
Application for plugging filed 4-27- 19 61
Application for plugging approved 4-27- 19 61
Plugging commenced 4-27 19 61
Plugging completed 4-27- 19 61
Reason for abandonment of well or producing formation No productive horizons encountered
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Faricius, Hill City, Kansas
Producing formation None Depth to top X Bottom X Total Depth of Well 4600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Water Sand	Fresh Water	80'	150'	8 5/8"	208'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set cement plug at 400' with twenty sacks of cement, filled hole with mud to 200' and set cement plug with twenty sacks of cement, filled hole with mud to 40' from surface, set plug with ten sacks of cement with two wires attached to plug and extending to surface.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Company
Address Atwood, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
J. W. Garner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.W. Garner
910 Enterprise Building Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of May, 1961

My commission expires October 15, 1963 Notary Public.

