

KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-147-00118-00-00

R

File No. 78-9 Location: NE NE SW
County: Phillips Sec. 16 Twp. 4 Rge. 19 (E) (W)
Name of Field or Pool: _____ Total Depth: 3607

I have this date completed supervision of plugging of:

Well No. 1 Lease Bales

Operator's Full Name John O. Farmer Inc

Complete Address: Russell, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Abandoned Oil Well ☒ Gas Well _____ Input Well _____ SWD Well _____ D & A _____

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour 11 AM Day 5 Month 2 Year 58

The above well was plugged as follows:

8 5/8" at 163' circulated with cement - 5 1/2" 3414' with 100 sax cement
behind - P.B. 3280', perforated 3212'.

Filled with sand to 3200', set 4 sax cement with dump bailer, pulled

2495', 5 1/2" - circulated hole with heavy mud through 5 1/2" - displaced

20 sax cement through 5 1/2" at 530' - heavy mud to 150', displaced

15 sax cement through 5 1/2" at 150', heavy mud to 35', set rock and

10 sax cement to bottom cellar.

West Supply Co. pump truck used for mudding and cementing.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: _____
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED

02-15-1958

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

Signed: _____
Well Plugging Supervisor

PLUGGING			
FILE	SEC 16	T 4	R 19W
BOOK	PAGE 78	LINE 9	