

KANSAS

*J*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 6 1972  
07-06-1972  
CONSERVATION DIVISION  
Wichita, Kansas

15-147-20158-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Good & Phillips Oil Company

Complete Address 3305 Mayberry Enid, Oklahoma

Lease Name Morgan Well No. 3

Location 400' FEL & 575' FSL of NE NW NW Sec. 15 Twp. 4 Rge. (E) (W) 19

County Phillips Total Depth 3370'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 3<sup>A</sup> Day 3 Month 7 Year 1972

The above well was plugged as follows:

RTD 3370' 8 5/8 csg set at 245' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Red G. Massey  
Well Plugging Supervisor

INVOICED

DATE 7/6/72  
INV. NO. 5999-U