



KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-147-20062-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1969
25-1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name R. W. Rine Drlg. Co.,

Complete Address: Suite 600 - 360 W Douglas Wichita, Kansas

Lease Name Reynolds Well No. 2

Location C SW SE Sec. 20 Twp. 4 Rge. 19 (E) (W) X

County Phillips Total Depth 3317'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Murfin Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 8:15P Day 3 Month 2 Year 1969

The Above well was plugged as follows:

RTD 3317' 8 5/8 csg set at 219' CWC Cmt Mat 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plugged rat hole with 2 sk cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Mamy
Well Plugging Supervisor

DATE 2/6/69
INV. NO. 9292-W