

KANSAS

24

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1970

CONSERVATION DIVISION
Wichita, Kansas

07-27-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-147-00165-00-00

Operator's Full Name Braden -Deem, Inc.

Complete Address 520 -200 E. 21st. Wichita, Kansas

Lease Name Kinter Well No. 1

Location SW NW SW Sec. 20 Twp. 4 Rge. (E) (W) 19

County Phillips Total Depth 3355

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 5:30P Day 22 Month 7 Year 1970

The above well was plugged as follows:

Total Depth 3355' 8 5/8 csg set at 134' cwc

5 1/2 csg set at 3354' cw 150 sk cmt.

5 1/2 csg PBTD 3230' with top perf. (3207)

Filled 5 1/2 csg W/sd. (3190-3230) Dumped 5 sk cmt W/dump bailer. (3140-3190)

Cutoff and recovered 2000' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/3 sk hulls, plug and 120 sk reg poz W/6% gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 7/28/70
INV. NO. 2293-U