

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-20057-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 18 1968  
11-18-1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Leland R. Baird

Complete Address: 1st. Nat'l Bank Bldg., Logan, Kansas *67646*

Lease Name Fischli Well No. 1

Location G S/2 SW SW Sec. 18 Twp. 4 Rge. 19 (E) (W) XX

County Phillips Total Depth 3530'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Murfin Drlg.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 2:15A Day 14 Month 11 Year 1968

The Above well was plugged as follows:

RTD 3530' 8 5/8 csg set at 215' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cmt.  
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo F. Murray*  
Well Plugging Supervisor

INVOICED

DATE 11/18/68  
INV. NO. 8835-W