

KANSAS

*P*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-137-20077-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 9 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
8-9-71

Operator's Full Name Leben, et al  
Complete Address 200 W. Douglas Wichita, Kansas  
Lease Name Finley Well No. 1  
Location C SW SW Sec. 28 Twp. 4 Rge. (E) (W) 22  
County Norton Total Depth 3780'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX  
Other well as hereafter indicated       
Plugging Contractor Co. Tools  
Address      License No.       
Operation Completed: Hour 8:30 P Day 5 Month 8 Year 1971

The above well was plugged as follows:

RTD 3780' 8 5/8 csg set at 209' cwc.  
Gunned pits, circulated heavy mud, set cementing plug at 1050' and displaced 100 sk  
cmt thru drill pipe. Heavy mud to 220' set cementing plug and displaced 25 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Maxey  
Well Plugging Supervisor

DATE 8-10-71

INV. NO. 4120-W