

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20070-00-00

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1971
CONSERVATION DIVISION
Wichita, Kansas

1-13-71

Operator's Full Name Leben et al,
Complete Address 200 West Douglas, Wichita, Kansas.
Lease Name Stone Well No. 1
Location CNW-NW Sec. 36 Twp. 4 Rge. (E) (W) 22
County Norton Total Depth 3675'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Leben Drilling, Incorporated,
Address Box #186, Great Bend, Kansas. License No.
Operation Completed: Hour 10:00 PM Day 8 Month 1 Year 1971

The above well was plugged as follows:

216'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 825'.

Circulated well with heavy mud. Pulled DP to 1050' and displaced 100 Sx. cement thru
DP from 1050' to 725'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols

Well Plugging Supervisor

DATE 1-13-71

INV. NO. 3205-W