

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20069-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1972
CONSERVATION DIVISION
Wichita, Kansas

1-3-72

Operator's Full Name Leben Oil Corporation,

Complete Address Box #486, Great Bend, Kansas.

Lease Name Archer Well No. A-2

Location CNW-NE Sec. 35 Twp. 4 Rge. (E) (W) 22

County Norton Total Depth 3704'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No. 670

Operation Completed: Hour 12:00 M Day 29 Month 12 Year 1971

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 175 Sx.
3653'--4 1/2" Production casing cemented on bottom with 100 Sx. Top of cement @ 3245'
(Temp. Survey). Well plugged back to 3626'. Top of Perforations @ 3615'.

Sanded well back to 3600' and set 5 Sx. cement with dump bailer. Pulled 4 1/2" casing
and squeezed well initially with 5 sacks hulls and 15 sacks gel and followed with
110 Cu. Ft. cement from 1025' to 700' then 12 sacks gel from 700' to 225' and followed
with 30 Cu. Ft. cement from 225' to 150' then 3 sacks gel from 150' to 30' and finally
10 Cu. Ft. cement from 30' to bottom of cellar. Maximum pump-in pressure--300#.
Final shut-in pressure--100#. (Mudding and cementing by Sun Cementing Inc.,).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Dinkel
Well Plugging Supervisor

DATE 1-4-72
INV. NO. 4844-11