

KANSAS

af
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15137-20064-0000

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
APR 3 - 1972
CONSERVATION DIVISION
Wichita, Kansas

4-3-72

Operator's Full Name Leben Oil Corporation,
Complete Address Box #486, Great Bend, Kansas.
Lease Name Archer Well No. A-1
Location CNE-SW Sec. 26 Twp. 4 Rge. (E) (W) 22
County Norton Total Depth 3583'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Rockhold Engineering, Incorporated,
Address Box #698, Great Bend, Kansas. License No. 670
Operation Completed: Hour 11:30 AM Day 29 Month 3 Year 1972

The above well was plugged as follows:

208'--8 5/8" Surface casing cement circulated with 175 Sx.
3570'--5 1/2" Production casing cemented on bottom with 100 Sx.
Sanded well back to 3550' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well initially with 5 sacks hulls and 15 sacks gel then 110 Cu. Ft.
cement from 1025' to 700' and followed with 12 sacks gel from 700' to 225' then 30
Cu. Ft. cement from 225' to 150' and followed with 3 sacks gel from 150' to 30' and
finally 10 Cu. Ft. cement from 30' to bottom of cellar. Maximum pump-in pressure--
250#. Final shut-in pressure-100#. (Mudding and cementing operations by Sun).

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 4-3-72
INV. NO. 5464-W