

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-147-20062-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 5 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 02-05-1969

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Favinger of Murfin Drlg. has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: R. W. Rine Drlg. Co.,

Complete Address: Suite 600 -- 360 W Douglas Wichita, Ks.

Lease Name: Reynolds Well No. 2

Location: G SW SE Sec. 20 Twp. 4 Rge. 19 (E)(W) X

County: Phillips Total Depth 3317 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Favinger was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 800' and displace
70 sk cement thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cement to base of cellar. Plug rat hole
with 2 sk cement.

Very truly yours,

Geo F. Massey
 Conservation Division Agent