

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

15-147-20211-00-00

JAN 5 1976
01-05-1976
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Copas of J. O. Farmer Drlg. has this

date requested permission to plug the following described well:

Mr. Copas guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Inc.

Complete Address: Box 352, 370 W. Wichita Ave., Russell, Ks.

Lease Name: Slinker Well No. 1

Location: SW NE SW Sec. 19 Twp. 4 Rge. (E)(W) 19

County: Phillips Total Depth 3400' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Copas was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 720' thru drill
pipe. Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Reo Wassup
Conservation Division Agent