



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. - 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

15-147-20057-00-00

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 18 1968  
 11-18-1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Ehrlick of Murfin Drlg. has this date requested permission to plug the following described well:

Mr. Ehrlick guarantees payment of the plugging fee.

Operator's full Name: Leland R. Baird

Complete Address: 1st. Nat'l Bank Logan, Ks.

Lease Name: Fischli Well No. 1

Location: C S/2 SW SW Sec. 18 Twp. 4 Rge. 19 (E)(W) XI

County: Phillips Total Depth 3530' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Ehrlick was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace  
70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Leo J. Massey  
 Conservation Division Agent