



15-137-20069-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1972

CONSERVATION DIVISION
Wichita, Kansas

1-3-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc. has this
date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Leben Oil Corporation,

Complete Address: Box #486, Great Bend, Kansas.

Lease Name: Archer XXX Well No. A-2

Location: CNW-NE Sec. 35 Twp. 4 Rge. (E)(W) 22

County: Norton Total Depth 3704 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 175 Sx.
3653'--4 1/2" Production casing cemented on bottom with 100 Sx. Top of
perforations @ 3615'.

Sand well back to 3600' and set 3 Sx. cement with Dump Bailer. Pull 4 1/2"
casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. ft.
cement, staged.

Very truly yours,

Conservation Division Agent