



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1968
CONSERVATION DIVISION
Wichita, Kansas
17-11-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Charles Harre of Thoroughbred Drilling Co., has this date requested permission to plug the following described well:

Mr. Harre guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company,

Complete Address: 4th Floor Petroleum Building, Tulsa, Oklahoma.

Lease Name: Elfride Sansom Well No. 1

Location: SE-SE-SE Sec. 34 Twp. 4 Rge. (E)(W) 22

County: Norton Total Depth 3683 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Harre was instructed to plug the well as follows:

208'--8 5/8" Surface pipe, cement circulated with 125 Sx.
Top of Dakota section @ 760'.

Circulate hole with heavy mud. Pull DP to 985' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Leave well open from 175' to surface as a potential fresh water well.

Very truly yours,

A. D. Nichols
Conservation Division Agent