



15-137-20064-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 3 - 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
4-3-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Leben Oil Corporation,

Complete Address: Box #486, Great Bend, Kansas.

Lease Name: Archer Well No. A-1

Location: CNE-SW Sec. 26 Twp. 4 Rge. (E)(W) 22

County: Norton Total Depth 3583' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 175 Sx.

3570'--5 1/2" Production casing cemented on bottom with 100 Sx.

Sand well back to 3550' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

*H. L. Nichols*  
Conservation Division Agent