

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

FEB 26 1987

API NUMBER 15-039-20244-00-00

LEASE NAME Beers

WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 23 TWP. 4 RGE. 27 (E) or (W)

COUNTY DeCATUR

LEASE OPERATOR Edmiston Oil Co

ADDRESS 1260 KSB Bldg, Wichita, Ks.

PHONE# (316) 265-5241 OPERATORS LICENSE NO. 5042

Date Well Completed 11/2/82

Character of Well Producer Oil

Plugging Commenced 2-12-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-12-87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? yes

Producing Formation Shale & Lime. Depth to Top 225 Bottom 2650 T.D. 3662

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 3/4	205'	NO
				4 1/2	3662	NO

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mix 100 SKS Econolite + 2 SKS Hulls + 65 SKS Elonalite let 2 hrs & mix 10 SKS of Lite Weight & Fill TO Surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BJ Titan Services License No. \_\_\_\_\_

Address 207 SW 2nd Box 27 Oakley

STATE OF KS COUNTY OF Logan MAR 2 1987

BJ Titan (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) William R. Fitzgerald

(Address) 416 Edgerton Oakley KS

SUBSCRIBED AND SWORN TO before me this 12 day of Feb, 1987

STATE CORPORATION COMMISSION

Marilyn E. Fox  
Notary Public

My Commission Expires: Nov. 14, 1989

CORPORATION DIVISION  
Wichita Kansas

3-12-87



FEB 26 1987

DRILLER'S LOG

COMPANY: Edmiston Oil Company  
801 First National Bank Bldg.  
Wichita, Kansas 67202

ROTARY DRILLING COMMENCED: October 3, 1972

ROTARY DRILLING COMPLETED: October 16, 1972

WELL NAME: BEERS No. 1

LOCATION: NE NE SE Sec. 23-4S-27W  
Decatur County, Kansas

CONTRACTOR: E. K. Edmiston Drilling Co., Inc.  
801 First National Bank Bldg.  
Wichita, Kansas 67202

CASING RECORD: Set 205' of 8-5/8" surface pipe with  
160 sx. cement; Ran 4 1/2" casing @ 3662'  
w/225 sx. cement.

L O G

Measurements from top of Kelly Bushing (Elevation 2547 K.B.)

Sand and clay	0 - 216
Shale and Sand	1124
Shale	1740
Sand	1868
Shale	2068
Anhydrite	2090
Shale	2375
Shale and Lime	2832
Shale	3105
Shale and Lime	3662 R.T.D.

The undersigned, Robt. K. Edmiston, Vice-President of E. K. Edmiston Drilling Co., Inc., hereby certifies on behalf of said company, that the above log is a true and correct log of the formations encountered in drilling the above well, as reflected by the daily drilling reports.

Robt. K. Edmiston  
Robt. K. Edmiston


STATE OF KANSAS }  
COUNTY OF SEDGWICK } SS:

BE IT REMEMBERED that on this 7th day of December, 1972, before me, the undersigned, a Notary Public within and for the County and State aforesaid, came Robt. K. Edmiston, known to me to be the same person who executed the foregoing instrument on behalf of E. K. Edmiston Drilling Company, Inc., and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

Commission Expires:  
November 9, 1973

Marilyn E. Fox  
Marilyn E. Fox, Notary Public  
STATE CORPORATE COMMISSION



MAR 2 1987  
CONSERVATION DIVISION  
Wichita, Kansas  
3-2-87