

15-039-00045-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Decatur County, Sec. 22 Twp. 4 Rge. (E) 27 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NW SW
Lease Owner Harry Gore
Lease Name Mazanek Well No. 1
Office Address 400 Brown Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 18 1951
Application for plugging filed October 18 1951
Application for plugging approved October 18 1951
Plugging commenced October 18 1951
Plugging completed October 18 1951
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	219'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 200'. Set plug and 1/2 sack of cotton seed hulls and 15 sacks of cement. Filled hole to 40' set plug and 1/2 sack of hulls and 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1951
CONSERVATION DIVISION
Wichita, Kansas

10-26-51

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Harry Gore
Address 400 Brown Bldg. Wichita, Kansas

STATE OF KANSAS, COUNTY OF MONTGOMERY, ss.
FLOYD W. HILD (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. THE VEEDER SUPPLY & DEVELOPMENT COMPANY
(Signature) Floyd W. Hild
P. O. Box 201, Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 24th day of October, 1951
Lester Lawson Notary Public

My commission expires July 11, 1952 28-3273-s 4-50-10M

PLUGGING
FILE SEC 22 T 4 R 27
BOOK PAGE 112 LINE 24

95-039-00045-00-00

Company Harry Gore

Sec. 22 T. 4 R. 27

Loc. NW NW SW

County Decatur County, Kansas

Farm Mazanek

No. 1

Total Depth 4135'

Comm. 10-6-51

Comp. 10-18-51

Shot or Treated


Contractor Weeder Supply Company

Drilled with Rig - D

Issued

No. of Bits -

No. of Days - 13



Casing
 20 in. 10 in
 15 1/2 8 1/4
 12 1/2 6 5/8
 13 3/8 5 3/16

Set 219' of 8-5/8" Casing Cemented with 140 sacks cement.

Elevation

Production

Figures Indicate Bottom of Formation

Formation	0	30	30	Tops:	
Surface Soil Rock	0	30	30	Heebner	- 3347
Clay	30	100	70	Brown Lime	- 3561
Sand Shale	100	140	40	Lansing K.C.	- 3574
Shale Shells	140	219	79	Base K.C.	- 3781
Blue Shale	219	610	391	Sandy Conglomerate	- 3963
Shale Shells	610	1100	490	White Chert	- 4019
Sand Shale	1100	1250	150	Arbuckle	- 4078
Shale Shells	1250	1595	345		
Sand Shale	1595	1660	65		
Shale Shells	1660	1905	245		
Sand Shale	1905	1990	85		
Red Bed Shale	1990	2185	195		
Anhydrite	2185	2215	30		
Shale Shells	2215	2330	115		
Lime Shale	2330	2530	200		
Sand Shale	2530	2600	70		
Lime Shale	2600	3435	835		
Lime	3435	3825	390		
Lime Shale	3825	3956	131		
Conglomerate	3956	4010	54		
Conglomerate Shale	4010	4030	20		
Cherty Conglomerate	4030	4080	50		
Lime	4080	4135	55		
Total Depth	4135'				

Plugged at 200' with 15 sacks cement.
 Plugged at 40' with 10 sacks cement.

PLUGGING
 FILE SEC 22 T 4 R 27
 BOOK PAGE 118 LINE 28