

15-137-0038-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1972
05-24-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Theodore Gore,
Complete Address 650 Fourth National Bank Building, Wichita, Kansas.
Lease Name Henry Well No. 4
Location CN/2--NW Sec. 2 Twp. 4 Rge. (E) (W) 24
County Norton Total Depth 3764'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Glenn & Smith Pipe Pulling Company,
Address 204 E. 6th, Ellinwood, Kansas. License No. 396
Operation Completed: Hour 5:00 PM Day 19 Month 5 Year 1972

The above well was plugged as follows:

306'--8 5/8" Surface casing, cement circulated with 175 Sx.
3763'--5 1/2" Production casing cemented on bottom with 100 Sx. Top of perforations @ 3614'.
Sanded well back to 3600' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (1119') and squeezed well initially with 5 sacks hulls and 11 sacks gel and followed with 110 Cu. Ft. cement from 1200' to 875' then 15 sacks gel from 875' to 275' and followed with 30 Cu. Ft. cement from 275' to 200' then 4 sacks gel from 200' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure --300#. Final shut-in pressure--150#. (Mudding and cementing by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Fisher
Well Plugging Supervisor

INVOICED

DATE 5/25/72
INV. NO. 5732-W