

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20267-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 13 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
6-13-73

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Edmiston Oil Company,

Complete Address 801 First National Bank Building, Wichita, Kansas.

Lease Name Beers Well No. 2 - A

Location C S/2 NE SE Sec. 23 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3664'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor E. K. Edmiston Drilling Company, Incorporated,

Address Above License No.     

Operation Completed: Hour 1:30 AM Day 11 Month 6 Year 1973

The above well was plugged as follows:

205'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement  
thru DP from 1250' to 925'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: K. L. Nichols  
Well Plugging Supervisor

DATE 6/13/73  
INV. NO. 7502-W