

**KANSAS
STATE CORPORATION COMMISSION**

CONSERVATION DIVISION AGENT'S REPORT

15-039-20085-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1969
CONSERVATION DIVISION
Wichita, Kansas

5-6-69

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Murfin Drilling Company and Nadel & Gussman,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name Petracek Well No. 1

Location App. CNE-NE Sec. 23 Twp. 14 Rge. (E) (W) 27

County Decatur Total Depth 3925'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drilling Company.

Address: 617 Union Center Building, Wichita, Ks. License No. _____

Operation Completed: Hour 8:45 PM Day 1 Month 5 Year 1969

The Above well was plugged as follows:

2 1/8" - 8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru
DP from 1250' to 925'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 10' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. F. Dehels
Well Plugging Supervisor

DATE 5/6/69

INV. NO. 9711-W