

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20022-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name J. C. Graves - J. N. Champlin,

Complete Address: 505 Union Center, Wichita, Kansas.

Lease Name Petracek Well No. 1

Location CSW-NE Sec. 23 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3931'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 5:00PM Day 13 Month 9 Year 1967

The Above well was plugged as follows:

241'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Dakota section from 1590' to 1770'.

Circulated hole with heavy mud. Pulled DP to 1800' and displaced 100 Sx. cement thru
DP from 1800' to 1480'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from 240'
to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1967 9-15-67

I hereby certify that the above well was plugged as herein stated.

CONSERVATION DIVISION
Wichita, Kansas

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 9/15/67
INV. NO. 6337-w