

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1972  
05-24-1972  
CONSERVATION DIVISION  
Wichita, Kansas

15-137-00144-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Theodore Gore,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Henry Well No. 1

Location NE-NE-NW Sec. 2 Twp. 4 Rge. (E) (W) 24

County Norton Total Depth 3737'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Smith & Glenn Pipe Pulling Company,

Address 20 1/2 E. 6th, Ellinwood, Kansas. License No. 396

Operation Completed: Hour 7:15 PM Day 19 Month 5 Year 1972

The above well was plugged as follows:

264'--8 5/8" Surface casing, cement circulated with 135 Sx.  
3734'--5 3/8" Production casing cemented on bottom with 100 Sx. No plug back nor perforations indicated.

Sanded well back to 3700' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (1015') and squeezed well initially with 5 sacks hulls and 11 sacks gel and followed with 110 Cu. Ft. cement from 1200' to 875' then 15 sacks gel from 875' to 275' and followed with 30 Cu. Ft. cement from 275' to 200' then 4 sacks gel from 200' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure--300#. Final shut-in pressure--150#. (Mudding and cementing by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: R. L. Fisher  
Well Plugging Supervisor

INVOICED

DATE 5/25/72

INV. NO. 5731-W