

8

DISTRICT CONSERVATION AGENT'S REPORT

TO: 15-137 - 00090-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 149-23
LOCATION NE NE SW
SEC. 2 TWP. 4 RGE. 24

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Radloff

Operator Jones Shelburne Farmer Address Russell, Kans

Field _____ County Norton

Total Depth 3833 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____
(Describe briefly the manner in which the well was plugged)

8 5/8" at 260' circulated with cement - 5 1/2" at ~~320~~ 3797'
with 100 sax cement behind.

Sand to 3790' set 4 sax cement with dump bailer, pulled 1600'
5 1/2" - mud to 260', set rock and 15 sax cement, mud to ~~350~~ 35'
set rock and 10 sax cement to bottom cellar.

Edw. J. Kelly
District Conservation Agent

Date 9-28-55

PLUGGING
FILE SEC. 2 T. 4 R. 24
BOOK PAGE 149 LINE 23

OCT 3 1955
10-03-1955
CONSERVATION DIVISION
Wichita, Kansas