

DISTRICT CONSERVATION AGENT'S REPORT

BR

TO:

15-039-00512-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. ~~220X~~ 27-50

LOCATION 34 NW NE

SEC. 36 TWP. 4 RGE. 27

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Wacha

Operator The Texas Co Address Box 1801 Wichita, Kans

Field _____ County Decatur

Total Depth 3580 Feet.

Plugging Contractor Jayhawk Pipe Pulling

Plugging Contractor's License No. 19

Address _____

(Describe briefly the manner in which the well was plugged)

10 5/4" at 700' circulated with 500 sax cement - 7" at 3579'

with 75 sax cement behind - Baker plugs at 3249', perforated at

3186' -

filled with sand to 3175', set 5 sax cement with dump bailer,

pulled 2079' 7", filled with mud to 250', set rock and 25 sax

cement, mud to 55', set rock and 15 sax cement to bottom

collar.

RECEIVED
STATE CORPORATION COMMISSION

E. J. Petty
District Conservation Agent

Date 5-9-54

PLUGGING
FILE SEC 36 T 4 R 27W
BOOK PAGE 22 LINE 30

CONSERVATION DIVISION
Wichita, Kansas

5-12-54