

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20248-00-00

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1972
11-20-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Edmiston Oil Company,
Complete Address 801 First National Bank Building, Wichita, Kansas.
Lease Name Bailey Well No. 1
Location N/2-NE-SE Sec. 35 Twp. 4 Rge. (E) (W) 27
County Decatur Total Depth 3708'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 7:15 AM Day 18 Month 11 Year 1972

The above well was plugged as follows:

248'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 110 Cu. Ft. cement
thru DP from 1300' to 975'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge. @ 40' with $\frac{1}{2}$ sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dickel
Well Plugging Supervisor

INVOICED

DATE 11/20/72

INV. NO. 6652-4