

*AL*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20180-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 5 1973  
*2-5-73*  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Incorporated,

Complete Address Box #18407, Wichita, Kansas.

Lease Name Skubal Well No. 2

Location SE-NE-NE Sec. 35 Twp. 4 Rge. (E) (W)27

County Decatur Total Depth 3889'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling,

Address Box #176, Chase, Kansas. License No. 683

Operation Completed: Hour 1:30 AM Day 30 Month 1 Year 1973

The above well was plugged as follows:

330'--8 5/8" Surface casing, cement circulated.  
3688'--5 1/2" Production casing cemented on bottom with 175 Sx. No plug back indicated.  
Top perforation @ 3174'.

Pushed plug to 3190', sanded back from 3190' to 3150' and set 5 Sx. cement with dump  
bailer. Pulled 5 1/2" casing (400') and squeezed well initially with 5 sacks hulls and  
13 sacks gel and followed with 110 Cu. Ft. cement from 1300' to 975' then 16 sacks  
gel from 975' to 335' and followed with 30 Cu. Ft. cement from 335' to 260' then 6  
sacks gel from 260' to 20' and finally 10 Cu. Ft. cement from 20' to bottom of  
cellar. Maximum pump-in pressure-500#, Final shut-in pressure-200#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*  
Well Plugging Supervisor

DATE 2/5/73  
INV. NO. 6934-W