

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20170-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1973
CONSERVATION DIVISION
Wichita, Kansas
2-5-73

Operator's Full Name Thunderbird Drilling, Incorporated,
Complete Address Box #18407, Wichita, Kansas.
Lease Name Skubal Well No. 1
Location SE-SE-NE Sec. 35 Twp. 4 Rge. (E) (W) 27
County Decatur Total Depth 3725'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Casing Pulling,
Address Box #176, Chase, Kansas. License No. 683
Operation Completed: Hour 9:15 AM Day 30 Month 1 Year 1973

The above well was plugged as follows:

330'--8 5/8" Surface casing, cement circulated.
3723'--5 1/2" Production casing cemented on bottom with 100 Sx. Stage Collar set @ 2111'
with 600 Sx. cement circulated to surface. Top perforations @ 3531'.
Squeezed 5 1/2" casing initially with 1 sack hulls and 30 Cu. Ft. cement from 3531' to
3400' then 21 sacks gel from 3400' to 1300' and followed with 50 Cu. Ft. cement from
1300' to 900' then 6 sacks gel from 900' to 300' and finally 45 Cu. Ft. cement from
300' to bottom of cellar. Maximum pump-in pressure-350#. Final shut-in pressure-
300#. (Mudding and cementing operations performed by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dickole
Well Plugging Supervisor

INVOICED

DATE 2/5/73
INV. NO. 6936-4