

KANSAS

W
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20255-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1973
1-8-73
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Edmiston Oil Company,

Complete Address 801 First National Bank Building, Wichita, Kansas.

Lease Name Mazanek Well No. 2-A

Location 100' N of CS/2-NE-SW Sec. 22 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3590'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor E. K. Edmiston Drilling Company, Incorporated,

Address 801 First Nat'l Bank Bldg., Wichita, Ks. License No.

Operation Completed: Hour 1:30 PM Day 4 Month 1 Year 1973

The above well was plugged as follows:

216'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 110 Cu. Ft. cement
thru DP from 1275' to 950'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Dicks
Well Plugging Supervisor

DATE 1/9/73
INV. NO. 6827-11