

KANSAS

18
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

18-039-20249-00-00

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1973

1-4-73

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Edmiston Oil Company, Inc.

Complete Address 801 First National Bank Building, Wichita, Kansas.

Lease Name Mazanek Well No. 2

Location S/2-NE-^{SW} ~~NW~~ Sec. 22 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 1800'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated Lost Hole

Plugging Contractor E. K. Edmiston Drilling Company, Inc.,

Address Above License No.

Operation Completed: Hour 1:15 PM Day 29 Month 12 Year 1972

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated with 185 Sx.
 Top of Dakota section @ 1050'. Lost circulation on bottom was unable to regain. On
 12/20/72 Pushed plug to 1125', sanded back from 1125' to 1350'. and displaced 150 Cu.
 Ft. cement thru DP @ 1350'. Plug slipped. On 12/21/72 pushed plug to 1160', plug stop-
 ped. Ran crushed rock from 1160' to 1070' and displaced 150 Cu. Ft. cement thru DP
 from 1070' to 620'. Left hole open until setting surface on alternate well. On 12/29/
 72 checked well, found bridge @ 122'. Filled well from 122' to bottom of cellar with
 40 Cu. Ft. cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Nichols*
Well Plugging Supervisor

DATE 1/4/73
INV. NO. 6811-W