

KANSAS

*X*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20168-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 31 1970  
CONSERVATION DIVISION  
Wichita, Kansas

7-31-70

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Tacha Well No. 5

Location SW-NE-SE Sec. 22 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3755'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 4:45 PM Day 29 Month 7 Year 1970

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru  
DP from 1200' to 875'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from  
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *R. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 7/31/70

INV. NO. 2317-W