

JS

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-20165-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1970
CONSERVATION DIVISION
Wichita, Kansas

7-24-70

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Tacha Well No. 4

Location SW-NW-SE Sec. 22 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3710'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 11:30 PM Day 21 Month 7 Year 1970

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement from
40' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/24/70
INV. NO. 2280-u

Signed: *H. L. Nichols*
Well Plugging Supervisor