

KANSAS

Form CP-3  
Rev. 6-4-68

CP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20147-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
3-30-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated & Consolidated Oil & Gas, Inc.,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Mazanek Well No. 1

Location NE-NE-NW Sec. 27 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3745'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor John O. Farmer, Incorporated.

Address Above License No.       

Operation Completed: Hour 8:30 PM Day 23 Month 3 Year 1970

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 150 Sx.

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 100 Sx. cement thru

DP from 1350' to 1025'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from

210' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

      

      

      

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 3-30-70

INV. NO. 1657-W