

KANSAS

2
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20270-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1973
CONSERVATION DIVISION
Wichita, Kansas
7-23-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Edmiston Oil Company,

Complete Address 801 First National Bank Building, Wichita, Kansas.

Lease Name Petrasek Well No. B-2

Location NW-SE-SE Sec. 26 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3654'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor E. K. Edmiston Drilling Company, Incorporated,

Address Above License No.

Operation Completed: Hour 9:30 AM Day 20 Month 7 Year 1973

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated . 200 Sx. on bottom and 100 Sx. thru 1" from top. Top of Dakotas @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 110 Cu. Ft. cement

thru DP from 1325' to 1000'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru

DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.

cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/29/73
INV. NO. 7698-W

Signed: W. L. Dickel
Well Plugging Supervisor