

KANSAS

AP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20226-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1972
CONSERVATION DIVISION
Wichita, Kansas
3-6-72

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Messman-Rinehart Oil Company,

Complete Address 1432 Wichita Plaza, Wichita, Kansas.

Lease Name Petracek Well No. 3

Location CNW-NE Sec. 26 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3640'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 6:30 PM Day 4 Month 3 Year 1972

The above well was plugged as follows:

322'--8 5/8" Surface casing, cement circulated with 235 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 340' and displaced 30 Cu. Ft. cement thru
DP from 340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 3-6-72

INV. NO. 5304-10