

15-039-19008-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 104-19  
LOCATION SE NE SE  
SEC. 26 TWP. 4 RGE. 27W

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Nellans Estate  
Operator Peel-Hardman Oil Co. Address R R #3 Box 144B Wichita, Kans  
Field \_\_\_\_\_ County Decatur

Total Depth 3542 Feet.

Plugging Contractor Bert Self

Plugging Contractor's License No. 48

Address \_\_\_\_\_  
(Describe Briefly the manner in which the well was plugged)

8 5/8" at 325' circulated with cement - 5 1/2" at 3530' with 125  
sax cement behind - P.B. to 3210', perforated 3190',  
Filled with chat to 3180', set 4 sax cement with dump bailer,  
pulled 2500' 5 1/2" - mudded hole to 300', set rock and 25 sax  
cement, mud to 35', set rock and 10 sax cement to bottom cellar.

E. L. Lett  
District Conservation Agent

Date 9-5-56

RECEIVED

10-9-56

PLUGGING  
FILE SEC 26 T. 4 R 27W  
BOOK PAGE 104 LINE 19