

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Drilling completed
June, 1954

#4

15-137-00592-00-00

API NUMBER _____

LEASE NAME Schoen "B"

WELL NUMBER #4

3960 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 2 TWP. 4S RGE. 24 (XXX)(W)

COUNTY Norton

Date Well Completed 6-12-54

Plugging Commenced 2:15 P.M.

Plugging Completed 10-5-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS P.O. Box 352, Russell, KS 67665

PHONE# (913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 15, 1988 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? Drilled prior to inception if not, is well log attached? Yes

Producing Formation of ACO-I Arbuckle Depth to Top 3796' Bottom 3799' T.D. 3799'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil & water	3796'	3799'	8-5/8"	280'	-0-
				5-1/2"	3796'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Down 5-1/2" casing @ 500# maximum pressure - mixed 25 sks. cement, then mixed 4 sks. hulls w/275 sks. cement and shut in @ 200#. Down annulus (8-5/8" casing) @ 300# maximum pressure - mixed 2 sks. hulls w/100 sks. cement and shut in @ 200#. The casing was perforated 3 shots @ 1650' prior to cementing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor John O. Farmer, Inc. License No. 5135

Address P.O. Box 352, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III (~~XXXXXXXXXXXXXXXXXXXX~~) (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and data herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665

RECEIVED
STATE CORPORATION COMMISSION
10-19-1988
OCT 19 1988
SUBSCRIBER DIVISION
CONSERVATION DIVISION
Wichita, Kansas

AND SWORN TO before me this 18th day of October, 19 88

Margaret A. Schulte
Notary Public

My Commission Expires: January 27, 1989

