

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 South Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-137-00529-00-00

API NUMBER Drilling completed 8-31-53

LEASE NAME Green

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 60 days.

WELL NUMBER #1

330 Ft. from N Section Line  
2310 Ft. from W Section Line

LEASE OPERATOR John O. Farmer, Inc.

SEC. 1 TWP. 4S RGE. 24 XXXXXX (W)

ADDRESS P.O. Box 352, Russell, KS 67665

COUNTY Norton

PHONE# (913) 483-3144 OPERATORS LICENSE NO. 5135

Drilling completed

Date Well Completed 8-31-53

Plugging Commenced 8-29-95

Plugging Completed 11:45 A.M.,

8-29-95

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 4, 1995 (date)  
by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? WELL LOG SENT TO KCC W/CP-1 on 8-3-95

Producing Formation Arbuckle Depth to Top 3803' Bottom 3812' T.D. 3812'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil	3803'	3812'	8-5/8"	255'	-0-
				5-1/2"	3805'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

The casing was perforated 2 shots @ 2080' and 2 shots @ 990' prior to cementing. Mixed 35 sks. down 8-5/8" w/100# hulls. Maximum pressure - 200#. Shut in @ 100#. Mixed 265 sks. w/400# hulls down 5-1/2". Maximum pressure - 1200#. Shut in @ 300#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License SEP 08 1995

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 7th day of September, 19 95

Margaret A. Schulte  
Margaret A. Schulte - Notary Public

