

15-039-20550-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Decatur SEC. 23 TWP. 4S RGE. 27W E/W
 Location as in quarters or footage from lines:
NE NE NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner A.L. Abercrombie, Inc.
 Lease Name Petracek #1 Well No. _____
 Office Address 801 Union Center Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 5-20-82
 Plugging completed 5-23-82
 Reason for abandonment of well or producing formation _____

~~XXXXXX~~ Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation _____ Depth to top _____ bottom _____ T.D. 3686'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	287'	none
				4-1/2"	3650'	1815'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged off bottom with sand to 3300' and ran 4 sacks cement. Shot casing @2217',
 2021' and 1828'. Pulled a total of 43 joints of 4-1/2" casing. Plugged well with
 5 sacks hulls, 20 sacks gel, 70 sacks cement, 15 sacks gel, 60 sacks cement, 8-5/8"
 plug, 10 sacks cement, 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

RECEIVED
 STATE CORPORATION COMMISSION

MAY 25 1982

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of May, 1982

My Commission expires:



Irene Hoover
 Notary Public.