

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20191-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1974

CONSERVATION DIVISION
Wichita, Kansas

10-15-74

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Zenith Drilling Corporation,

Complete Address Suite 600, 200 W. Douglas, Wichita, Kansas.

Lease Name Walters Well No. 1

Location CNW-SE Sec. 17 Twp. 4 Rge. (E) (W) 33

County Rawlins Total Depth 4460'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 2:30 PM Day 9 Month 10 Year 1974

The above well was plugged as follows:

291'--8 5/8" Surface casing, cement circulated with 210 Sx.
Top of Dakota section @ 1725'.

Circulated hole with heavy mud. Pulled DP to 1950' and displaced 110 Cu. Ft. cement
thru DP from 1950' to 1625'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP ~~to~~, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 10/16/74
INV. NO. 117-W