

KANSAS

A STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1971
CONSERVATION DIVISION
Wichita, Kansas
9-9-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20124-00-00

Operator's Full Name Murfin Drilling Company,
Complete Address 617 Union Center Building, Wichita, Kansas.
Lease Name Minney Well No. 1
Location CNE-NW Sec. 17 Twp. 4 Rge. (E) (W) 33
County Rawlins Total Depth 4320'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 9:00 PM Day 3 Month 9 Year 1971

The above well was plugged as follows:

275'---8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1825'.

Circulated hole with heavy mud. Pulled DP to 2050' and displaced 100 Sx. cement
thru DP from 2050' to 1725'. Pulled DP to 310' and displaced 25 Sx. cement thru DP
from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 9-10-71

INV. NO. 4312-W