

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-00011-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1974
CONSERVATION DIVISION
Wichita, Kansas
3-5-74

Operator's Full Name Beren Corporation,

Complete Address 1130 Wickers KSB&T Building, Wichita, Kansas.

Lease Name Walters Well No. 1

Location NE-NE-SW Sec. 17 Twp. 4 Rge. (E) (W)33

County Rawlins Total Depth 4830'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:00 PM Day 28 Month 2 Year 1974

The above well was plugged as follows:

303'--8 5/8" Surface casing, cement circulated with 250 Sx.
4759'--5 1/2" Production casing cemented on bottom with 250 Sx. Top perforations from
4051' to 4081', no plug-back indicated. DV Tool @ 2785' with 175 Bbl. Chem-Pak.
DV tool leaked, squeezed with 225 Sx. cement.

Sanded well back to 4025' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(1635') and squeezed well initially with 5 sacks hulls and 8 sacks gel and followed
with 110 Cu. Ft. cement from 1925' to 1600' then 32 sacks gel from 1600' to 320'
then 30 Cu. Ft. cement from 320' to 250' and followed with 5 sacks gel from 250' to
40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in
pressure-300#. FSIP-150#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/5/74

INV. NO. 8704-W

Signed: M. L. Nichols
Well Plugging Supervisor