

KANSAS

B
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-20184-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1970

CONSERVATION DIVISION
Wichita, Kansas

10-12-70

Operator's Full Name Mack Oil Company,

Complete Address 812 Union Center, Wichita, Kansas.

Lease Name Alstrom Well No. 1

Location CSE-NW Sec. 31 Twp. 4 Rge. (E) (W)29

County Decatur Total Depth 4115'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 12:15 PM Day 8 Month 10 Year 1970

The above well was plugged as follows:

315'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1650' and displaced 100 Sx. cement thru
DP from 1650' to 1325'. Pulled DP to 340' and displaced 25 Sx. cement thru DP from
340' to 275'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 10-12-70

INV. NO. 2664-W