

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20148-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1973
2-26-73
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beacon Resources Corporation.

Complete Address 1000 Century Plaza Building, Wichita, Kansas.

Lease Name Chandler-Weber Well No. 1

Location CNW-NW Sec. 23 Twp. 4 Rge. (E) (W) 35

County Rawlins Total Depth 4734'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 3:00 PM Day 22 Month 2 Year 1973

The above well was plugged as follows:

289'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1775'.

Circulated hole with heavy mud. Pulled DP to 2000' and displaced 110 Cu. Ft. cement
thru DP from 2000' to 1675'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu.Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 2/28/73
INV. NO. 7063-u