

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1969
CONSERVATION DIVISION
Wichita, Kansas

15-039-00480-00-01

Operator's Full Name Texaco, Incorporated,

Complete Address 614 Bitting Building, Wichita, Kansas.

Lease Name R. L. Skubal Well No. B-1W

Location NE-NE-NE, Sec. 35 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3880'

Abandoned Oil Well Gas Well Dual-
Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Halliburton Services,

Address E. 8th Street, Hays, Kansas. License No.

Operation Completed: Hour 12:00 M Day 25 Month 10 Year 1969

The above well was plugged as follows:

520'--8 5/8" Surface casing, cement circulated.
3671'--4 1/2" Casing, cement circulated with 800 Sx. Well plugged back to 3629'. Per-
forations from 3589' ~~xxx~~ to 3518' and 3250' to 3245'. Production packers set @ 3264'
and 3230'.

Squeezed well initially with 45 Sx. cement from 3629' to 3050' then 13 sacks gel from
3050' to 650' and finally 40 Sx. cement from 650' to bottom of cellar. Maximum pump-
in pressure-950#. Final shut-in pressure-900#. (Mudding & Cementing operations per-
formed by Halliburton Services).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/3/69
INV. NO. 765-4

Signed: N. L. Nichols
Well Plugging Supervisor