

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-05150-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 5 1967
9-5-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Phillips Petroleum Company

Complete Address: Box 287 Great Bend, Kansas

Lease Name Reeves Well No. 1

Location App. C SE SE Sec. 23 Twp. 4 Rge. 34 N (2) (W) X

County Rawlins Total Depth 4612

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 3: P Day 31 Month 8 Year 1967

The Above well was plugged as follows:

RTD 4612' 8 5/8 csg set at 315' cwc.

4 1/2 csg set at 4532' cw 90 sc cement.

PB at ~~4493~~ with top perf at 4204'

Pumped cement and plug to 2995 with 1000 lbs. pres.

Shot off and recov. 1745' of 4 1/2 csg.

Pumped down 8 5/8 csg with 24 sc gel to 600'-Followed with 80 sc cement with top at

315'-Followed with 3 sc gel and 20 sc ^{cem.} ~~gel~~ to 180'- Followed with 3 sc gel and 5 sc cem.

to base of cellar. Shutin pres 600 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/5/67

INV. NO. 6257-4

Signed: Leo F. Messing
Well Plugging Supervisor