

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20042-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1969
CONSERVATION DIVISION
Wichita, Kansas
6-12-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Stonehenge Oil Company, Incorporated,

Complete Address: 711 Franklin Building, Tulsa, Oklahoma.

Lease Name Mayfield Well No. 1

Location NE-NE Sec. 10 Twp. 4 Rge. (E) (W) 35

County Rawlins Total Depth 5110'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones, Incorporated,

Address: 830 Sutton Place, Wichita, Kansas. License No. _____

Operation Completed: Hour 2:45 PM Day 9 Month 6 Year 1969

The Above well was plugged as follows:

302'--8 5/8" Surface casing, cement circulated with 275 Sx.

Top of Dakota section @ 1875'. (Land owner requests surface casing be left open to be used as a potential fresh water well.)

Circulated hole with heavy mud. Pulled DP to 1950' and displaced 100 Sx. cement thru

DP from 1950' to 1625'. Pulled DP to 335' and displaced 25 Sx. cement thru DP.

Pulled DP to 275' and circulated clear water to surface in order to clear casing for completion

as a fresh water well. (Signed Authorization attached)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/12/69

INV. NO. 9931-W

Signed: H. L. Diebel
Well Plugging Supervisor



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg.
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 12 1969
 CONSERVATION DIVISION
 Wichita, Kansas

6-12-69

AUTHORIZATION

The undersigned, owner of the following described land, to

wit: NE/4-NE/4 of Sec. 10 Twp. 4S Rge. 35 W

Rawlins County, Kansas; hereby requests

that Well No. 1 located in NE/4 of Sec. 10 Twp. 4S

Rge. 35 W be left open above the fresh water protecting

bridge set at 1950' and 335' feet, to be used as a fresh water well

and I hereby authorize Stonehenge Oil Company, Inc.,

well owner, to so complete the abandonment of said well.

Witnessed by M. L. Nichols

Leonard E. Mayfield
(Land Owner)

Leonard Mayfield

Dated at Atwood, Kansas, this 9th day of

June, 1969.